

DATE : 10/03/2018

Item	Location	L (m)	W (m)	H (m)	No.	Area (m2)	Volume (m3)	Length (m)	Quantity of Materials	Unit
REPAIR OF DILAPIDATED WATER LINE SYSTEM ON RSCC THE BUILDING										
Installation of temporary scaffoldings										
									1.00	lot
	Formlumber								200.00	bd.ft.
	CWN assorted								4.00	kgs
	Hacksaw Blade								2.00	pcs.
Chipping Works (Concrete Masonry and Wall Tiles)										
						17.50			1.00	lot
	Unit 1 - Infants Room	3.00	0.50			1.50				
	Unit 2 -Toddler's Room	3.00	0.50			1.50				
	Unit 3 - Infirmary Room	5.00	0.50			2.50				
	Unit 4 - Nurse Station	3.00	0.50			1.50				
	Unit 5 - Observation Room	3.00	0.50			1.50				
	Unit 6 - Conference Room	1.00	0.50			0.50				
	Unit 7 - Adjacent to Records Room	5.00	0.50			2.50				
	Unit 8 - Center Head's Office	3.00	0.50			1.50				
	Unit 9 - Admin Office	3.00	0.50			1.50				
	Unit 10 - Guest Room 1	3.00	0.50			1.50				
	Unit 11 - Guest Room 2	3.00	0.50			1.50				
	Masonry / Concrete Penetration								1.00	lot
Supply and Installation of new piping for clean water line; reinstall removed fixtures and accessories										
									1.00	lot
	25mm Ø SDR13.5 HDPE Pipe x 100mts								2.00	rolls
	20mm Ø PVC Pipe x 3mts								18.00	pcs
	25mm Ø x 20mm Ø GI Tee Reducer								12.00	pcs
	25mm Ø x 90 Deg. GI Elbow								36.00	pcs
	20mm Ø GI Caps								20.00	pcs
	20mm Ø x 20mm Ø PVC Tee								33.00	pcs
	20mm Ø x 90 Deg. PVC Elbow								22.00	pcs
	3/4" Brass Outdoor Tap								2.00	pcs
	1" Ø Brass Check Valve								2.00	pcs
	1" Ø Brass Gate Valve								3.00	pcs
	Teflon Tape								30.00	pcs
	PVC Solvent Cement								5.00	s-cans
Dismantling and replacement of damage ceilings										
	Nurse Station	4.70	6.50			30.55				
	Toddlers Comfort Rooms	1.50	1.80			2.70				
	Infants Comfort Rooms	1.50	1.80			2.70				
	Comfort Rooms at 2nd Floor	2.50	2.00			5.00				
	Cement fiber Hardiflex, 4' x 8' x 1/4"					40.95			14.00	pcs.
	Formlumber								204.75	bd.ft.
	CWN assorted								1.00	kgs
	Flat head metal Screw								700.00	pcs.
	Hacksaw Blade								2.00	pcs.
Masonry Works and Installation of new tiles										
	Unit 1 - Infants Room	3.00	0.60			1.80				
	Unit 2 -Toddler's Room	3.00	0.60			1.80				
	Unit 3 - Infirmary Room	5.00	0.60			3.00				
	Unit 4 - Nurse Station	3.00	0.60			1.80				
	Unit 5 - Observation Room	3.00	0.60			1.80				
	Unit 6 - Conference Room	1.00	0.60			0.60				
	Unit 7 - Adjacent to Records Room	5.00	0.60			3.00				
	Unit 8 - Center Head's Office	3.00	0.60			1.80				
	Unit 9 - Admin Office	3.00	0.60			1.80				
	Unit 10 - Guest Room 1	3.00	0.60			1.80				
	Unit 11 - Guest Room 2	3.00	0.60			1.80				
	200 x 300mm Wall Tiles					21.00			350.00	pcs.
	Tile adhesive, 25kg								6.00	bags
	Tile grout. 2kg								3.00	bags

	Portland Cement							4.00	bags
	Acrylic Flat Latex (3 Coats)							4.00	liter
	Acrylic Gloss Latex							4.00	liter
	Sand Paper							10.00	leaf
	Mixing plate							2.00	pc
	3" Paint brush							2.00	pc
Painting Works								1.00	lot
Ceiling	Acrylic Flat Latex					40.95		2.00	4 Liter
	Acrylic Gloss Latex							4.00	4 Liter
	Gypsum Putty							2.00	4 Liter (7Kg)
	Masking Tape							3.00	roll
	Sand Paper							7.00	leaf
	Putty Knife							2.00	pcs
	Spatula							2.00	pcs
	Baby roller, 6"							2.00	pcs
	Roller re-fill, 6"							2.00	pcs
	Mixing plate							2.00	pcs
	3" Paint brush							2.00	pcs
	1" Paint brush							2.00	pcs

Prepared by:


Engr. Jess Valer V. Avisado
 Project Development Officer III