



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 6127858
Procuring Entity DEPARTMENT OF SOCIAL WELFARE AND DEVELOPMENT - REGION V
Title Labor and materials for the Repair of Dilapidated Water Line System on RSCC Building
Area of Delivery Albay

Solicitation Number:	NF 1902-0116	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	4
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Services	Date Published	31/03/2019
Approved Budget for the Contract:	PHP 165,676.00	Last Updated / Time	31/03/2019 00:00 AM
Delivery Period:	36 Day/s	Closing Date / Time	08/04/2019 09:00 AM
Client Agency:			
Contact Person:	Eva D. Bañares Head, BAC Secretariat Magnolia St., PBN Buragwis, Legazpi City Albay Philippines 4500 63-52-4805670 63-52-4805670 fo5bacsec@gmail.com		

Description

Labor and materials for the Repair of Dilapidated Water Line System on RSCC Building

I. Installation of Temporary Scaffoldings - 1 Lot

Formlumber - 200bd. Ft.

Assorted CWN - 4kgs

Hacksaw Blade - 2 pcs

Foreman

Skilled labor

Helper

II. Perform thorough inspection of existing water pipeline; ensure proper connection & layout - 1 lot

Foreman

Skilled labor

Helper

III. Chipping works on concrete walls and existing wall tiles; removal of existing toilet fixtures in good condition for reinstallation - 1 lot

Foreman

Skilled labor

Helper

Electric drill

Electric Grinder

IV. Supply and installation of new pipe and fittings; all water supply will originate from water tank; perform hydro test to ensure zero tolerance from leak - 1 lot

25mm Ø SDR13.5 HDPE Pipe x 100mts - 2 rolls

20mm Ø UPVC Pipe x 3mts - 18pcs
25mm Ø x 20mm Ø GI Tee Reducer - 12pcs
25mm Ø x 90 Deg. GI Elbow - 36pcs
20mm Ø GI Caps - 20pcs
20mm Ø x 20mm Ø UPVC Tee -33pcs
20mm Ø x 90 Deg. UPVC Elbow - 22 pcs
3/4" Brass Outdoor Tap - 2pcs
1" Ø Brass Check Valve - 2pcs
1" Ø brass Gate Valve - 3pcs

Teflon Tape - 30pcs
PVC Solvent Cement - 5 s-cans
Foreman
Skilled labor
Helper

V. Supply and install new wall tiles (affected areas with client's approval), masonry & plastering works; Reinstallation of removed toilet fixtures - 1 lot

200 x 300mm Wall tiles - 292pcs
Tile adhesive, 25kg - 5 bags
Tile grout, 2kg - 3bags
Pozzolan Cement - 3 bags
Acrylic Flat Latex (3 coats) - 4 liters
Acrylic Gloss Latex - 4 liters
Sand paper - 10 leaves
Mixing plate - 2pcs
3" paint brush - 2pcs
Foreman
Skilled labor
Helper

VI. Dismantling of dilapidated ceilings due to water leak; Supply and installation of hardiflex, ensure zero tolerance of adjoining panels - 35.95 sq.m.

Cement fiber hardiflex, 4' x 8' x 1/4" - 12pcs
Flat head metal screw - 600pcs
Blind rivets - 2 boxes
Acrylic Flat Latex - 2 gal
Acrylic Gloss Latex - 4 gal
Gypsum Putty - 2, 4liters
Masking tape - 3 rolls
Sand paper - 6 leaves
Putty Knife - 2 pcs
Spatula - 2 pcs
Baby roller, 6" - 2pcs
Roller re-fill, 6" - 2pcs
Mixing plate - 2pcs
3" Paint Brush - 2pcs
1" Paint Brush - 2pcs
Foreman
Skilled labor
Helper
Electric Drill

Note: Please download attached documents for your reference

Created by Nerichelle R Bobis

Date Created 30/03/2019

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.