



Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number 6677188
Procuring Entity DEPARTMENT OF SOCIAL WELFARE AND DEVELOPMENT - REGION V
Title Labor and Materials for waterproofing and tile works of DSWD FOV Pantawid Building Roof Deck
Area of Delivery Albay

Solicitation Number:	NF 1911-0667 (2020)	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Bid Supplements	0
Classification:	Goods	Document Request List	0
Category:	Construction Projects	Date Published	21/11/2019
Approved Budget for the Contract:	PHP 424,569.00	Last Updated / Time	21/11/2019 00:00 AM
Delivery Period:	52 Day/s	Closing Date / Time	25/11/2019 01:00 AM
Client Agency:			
Contact Person:	Eva D. Bañares Head, BAC Secretariat Magnolia St., PBN Buragwis, Legazpi City Albay Philippines 4500 63-52-4805670 63-52-4805670 fo5bacsec@gmail.com		

Description

Labor and Materials for waterproofing and tile works of DSWD FOV Pantawid Building Roof Deck

I. Clearing Works and Chipping Works (249.64 sq.m)

I.A. All surfaces should be clean, dry, and free from grease, oil, or dust; Remove all loose material. Surface irregularities need to be smoothed. Dampen clean surface with water.

___ days Foreman
 ___ days Skilled Labor
 ___ days Helper
 ___ days Handtools
 ___ days Grinder with Diamond Cutting Desk

I.B. All surfaces should be clean, dry, and free from grease, oil, or dust; Remove all loose material. Surface irregularities need to be smoothed. Dampen clean surface with water.

___ days Foreman
 ___ days Skilled Labor
 ___ days Helper
 ___ days Handtools
 ___ days Grinder with Diamond Cutting Desk

II. Waterproofing Works (252.14 sq.m)

II. A. Spray water to dampen surface; Use a trowel, stiff, or Tambico brush applying the first coat horizontally; Let dry for 2 to 3 hours. Apply second coat vertically. The coat should have a thickness of 2mm. Perform Flood Test to Allow Zero Tolerance from Leakage (2-coat)

101 gals Flexible Cementitious Waterproofing
 10 pcs Big Tampico Brush
 1 set Construction Safety Mask (50pcs)
 1 roll Sackoline Blue Sack-8ft wide
 ___ days Foreman
 ___ days Skilled Labor
 ___ days Helper
 ___ days Handtools

III. Concrete and Tile Works (249.64 sq.m)

III. A . Supply and Installation of outdoor floor tile above waterproofing material; ensure proper elevation/cleavae to designated downspouts; Perform Flood Test to Allow Zero Tolerance from Leakage

1561 pcs 400mmx400mm Outdoor Floor Tiles
 63 bags Portland Cement
 4 cu.m Washed Sand
 50 bags Tile grout, 2kg
 2 Unit Water Drum
 50 In.m Nylon Wire
 ___ days Foreman
 ___ days Skilled Labor
 ___ days Helper
 ___ days Handtools
 ___ days Grinder with Diamond Cutting Disk

IV. Plumbing Works (1 lot)

IV.A Supply and Installation of Plumbing fixtures; ensure proper elevation to avoid stagnant water; Perform Flood Test to Allow Zero Tolerance from Leakage
21 pcs 3" Ø PVC Elbow
5 pcs 3" Ø PVC Wye
18 pcs 3" Ø PVC Coupling
9 pcs Flooring Drain w/ Sediment Cast Bucket, 4"x4"
4 liters Pipe Sealant
____ days Foreman
____ days Skilled Labor
____ days Helper

Created by Eva D. Bñares

Date Created 20/11/2019

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.