

DRN: V-FO-AD-BGMS-A-PR-24-05-29014-5
 End-User: ASD/ BGMS

DEPARTMENT OF SOCIAL WELFARE AND DEVELOPMENT FIELD OFFICE V
 Regional Government Center, Rawis, Legazpi City, Albay
REQUEST FOR QUOTATION

Company Name: _____	PR No.: <u>NF 2405-0329</u>
Company Address: _____	Date: <u>June 03, 2024</u>
Contact No. / Email Address: _____	Mode of Procurement: <u>Sec.53.9 Small Value Procurement</u>
PHIGEPS Certificate No.: _____	TIN No.: _____

Please quote your lowest government price for the following item(s) specified below. Check/tick the "COMPLY" box if bidder complies with the specifications. A quotation containing unchecked/unticked "COMPLY" boxes would be automatically rated as "FAILED".

ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION AND SPECIFICATIONS	Kindly tick the box to signify compliance to the specs.	UNIT COST	TOTAL COST
	1	lot	REPAIR OF PLUMBLING SYSTEM OF PHASE 1 & 2 OF DSWD FO V, RAWIS, LEGAZPI CITY	<input type="checkbox"/> Comply	P	P
ABC: Php 121,059.08						

IMPORTANT REMINDERS:

- Price quotation/s must be valid for a period of 120 calendar days from the date of submission.
- DELIVERY PERIOD: Fifteen (15) Calendar Days upon receipt of Purchase Order (PO)
- PLACE OF DELIVERY: DSWD FO V, Rawis, Legazpi City
- The Project shall be AWARDED as follows: (a) as one contract (b) separate contracts per lot (c) separate contracts per item
- TERM OF PAYMENT: CHARGED ACCOUNT, unless specified.
- LIQUIDATED DAMAGES: One-Tenth Of One Percent (0.001) of the cost of the unperformed portion of the contract for every day of delay. Once the cumulative amount of liquidated damages reaches ten percent (10%) of the amount of the contract, the DSWD FOV may suspend or terminate the contract, without prejudice to other courses of action and remedies available under the circumstances.
- Required documents to submit:
 - PHIGEPS Certification Number
 - Valid Mayor's or Business Permit
 - Latest Income Tax Return
- As a condition for AWARD, you will be required to submit:
 - Omnibus Sworn Statement for Contract City Thousand Pesos (Php50,000.00) and above.
- For any clarifications, you may contact the BAC Secretariat at procurement.fod@dswd.gov.ph or 0910-217-0818.
- Submit your quotation duly signed by you or your duly authorized representative not later than the deadline on **JUN 10 2024 12:00 pm**

JUDEX DONNEL G. LLAMOSO
 AO IV Head PROCUREMENT

[Signature]
 BEN GENI B. WERANAY
 Signature over Printed Name of Bidder

Signature over Printed Name of Bidder/Authorized Representative



BILL OF QUANTITIES

DRN: _____

Name of Project: Repair of Plumbing System in Rawis Office - Phase 1 and Phase 2	Location: Regional Government Center Site, Rawis, Laguna City, Albay
Total Project Cost:	Project Duration: 19.00 Calendar Days
Source of Fund: To be funded	Mode of Procurement:
Date:	Source of Manpower:

Item No.	Item Description	Quantity	Unit	Material Cost	Labor Cost	Equipment Cost	Unit Cost	Amount
I. General Requirements								
1.10	Construction Safety and Health	19.00	day					
1.20	General Supervision	19.00	day					
SUB - TOTAL (General Requirements)								
II. Repair of Septic Tank and Re piping at Phase 1								
2.10	Plumbing Works	1.00	lot					
2.20	Excavation Works	22.50	cu.ft					
2.30	Removal of sludge and replacement of suitable materials	0.20	cu.m					
2.40	Concreting Works	0.20	cu.m					
2.50	Waterproofing Works	18.00	sq.m					
2.60	Manual Cleaning and Removal of wastes and sludge	1.00	septic tank					
SUB - TOTAL (Repair of Septic Tank and Re piping at Phase 1)								
III. Repair of leaks (Phase 2)								
3.10	Chipping Works	3.42	sq.m					
3.20	Plumbing Works	1.00	lot					
3.30	Tile Works	3.42	sq.m					
SUB - TOTAL (Repair of leaks (Phase 2))								
TOTAL PROJECT COST								

 Prepared by _____

Republic of the Philippines
DEPARTMENT OF SOCIAL WELFARE AND DEVELOPMENT
FIELD OFFICE V
Rawis, Legazpi City, Albay

Project: Repair of Plumbing System in Rawis Office - Phase 1 and Phase 2
Location: Regional Government Center Site, Rawis, Legazpi City, Albay
ABC:
Duration: 19 calendar days
Subject: Detailed Estimate

Item No.	Particulars	Physical Target		Unit Cost	Amount
I	Estimated Direct Cost (DC)				
	General Requirements				
1.1	Construction Safety and Health	19	day		
A	Material	Quantity	Unit		
	1 Safety Helmet	19.00	day		
	2 Safety Goggles	19	day		
	3 Safety Gloves	19	day		
	Sub-Total of A				
B	Labor	No. of Worker	No. of days	Daily Rate	Amount
	1 Safety Officer	1	5		
	Sub-Total of B				
	Direct Cost (A+B)				
	Indirect Cost (10%)				
	VAT: 5% x (DC + IC)				
	Total Item Cost				
1.2	General Supervision	19	day		
A	Labor	No. of Worker	No. of days	Daily Rate	Amount
	1.1 Construction Foreman	1	19		
	Sub-Total of A				
	Direct Cost (A)				
	Indirect Cost (20%)				
	VAT: 5% x (DC + IC)				
	Total Item Cost				
II	Repair of Septic Tank and Repiping at Phase 1				
2.1	Plumbing Works	1	lot		
	Labor and materials for replacement and repair of sanitary pipes at Rawis Phase 1 communal CR.				
A	Material	Quantity	Unit	Unit Cost	Amount
	1 100mmØ PVC Pipe series 1000	8	pc		
	2 100mmØ PVC Elbow, 45Ø	2	pc		
	3 4"x4" PVC Wye	4	pc		
	4 100mmØ Clean Out	3	pc		
	5 PVC Cement, 400cc	2	can		
	6 Consumables (5% of material cost)	1	lot		
	Sub-Total of A				
B	Labor	No. of Worker	No. of days	Daily Rate	Amount
	Skilled Worker	1	3		
	Unskilled Worker	1	3		
	Sub-Total of B				
C	Equipment	Quantity	No. of days	Daily Rental	Amount
	Grinder	1	1		
	Minor Tools (10% of Labor Cost)	Quantity	Unit	Unit Cost	Amount
		1	lot		
	Sub-Total of C				
	Direct Cost (A+B+C)				
	Indirect Cost (20%)				
	VAT: 5% x (DC + IC)				
	Total Item Cost				
2.2	Excavation Works	22.5	cu.m.		
A	Excavation of soil on top of the sanitary pipes to be replaced				
	Labor	No. of Worker	No. of days	Daily Rate	Amount
	Unskilled Worker	2	3		
	Sub-Total of A				
B	Equipment	Quantity	No. of days	Daily Rental	Amount
	Minor Tools (10% of Labor Cost)	1	lot		
	Sub-Total of B				
	Direct Cost (A+B+C)				
	Indirect Cost (20%)				
	VAT: 5% x (DC + IC)				
	Total Item Cost				

2.3	Removal of sludge and replacement of suitable materials Removal of at least 0.20 meter - thick of sludge and gravel fill to be replaced with suitable filling materials	0.2	cu.m.				
A	Material		Quantity	Unit	Unit Cost	Amount	
	1 Filling Materials		0.5	cu.m			
	2 Crushed Gravel 3/4"		0.5	cu.m			
					Sub-Total of A		
B	Labor		No. of Worker	No. of days	Daily Rate	Amount	
	Skilled Worker		1	1			
	Unskilled Worker		1	1			
					Sub-Total of B		
C	Equipment		Quantity	No. of days	Daily Rental	Amount	
	Minor Tools (10% of Labor Cost)		1	lot			
					Sub-Total of C		
					Direct Cost (A+B+C)		
					Indirect Cost (20%)		
					VAT: 5% x (DC + IC)		
					Total Item Cost		
2.4	Concreting Works Labor and materials for concreting of base of leaching well.	0.2	cu.m				
A	Material		Quantity	Unit	Unit Cost	Amount	
	1 Portland Cement (40 kg)		4	bag			
	2 Concrete Epoxy A & B		1	lit			
	3 Crushed Gravel 3/4"		0.5	cu.m			
	4 Washed Sand		0.5	cu.m			
	5 10mm dia RSB Grade 33 at 300mm O.C.B.W		4	pc			
	6 GI Tie Wire #16		1	kg			
	7 Consumables (5% of material cost)		1	lot			
					Sub-Total of A		
B	Labor		No. of Worker	No. of days	Daily Rate	Amount	
	Skilled Worker		1	2			
	Unskilled Worker		2	2			
					Sub-Total of B		
C	Equipment		Quantity	No. of days	Daily Rental	Amount	
	Minor Tools (10% of Labor Cost)		1	lot			
					Sub-Total of C		
					Direct Cost (A+B+C)		
					Indirect Cost (20%)		
					VAT: 5% x (DC + IC)		
					Total Item Cost		
2.5	Waterproofing Works Application of two (2) coats of waterproof coating on interior surfaces of the septic tank	18	sq.m.				
A	Material		Quantity	Unit	Unit Cost	Amount	
	1 Waterproof Coating		6	gal			
	2 Roller 6" with tray		2	set			
	3 Paint Brush 3"		4	pc			
	4 Consumables (5% of material cost)						
					Sub-Total of A		
B	Labor		No. of Worker	No. of days	Daily Rate	Amount	
	Skilled Worker		1	1			
	Unskilled Worker		1	1			
					Sub-Total of B		
C	Equipment		Quantity	Unit	Unit Cost	Amount	
	Minor Tools (10% of Labor Cost)		1	lot			
					Sub-Total of C		
					Direct Cost (A+B+C)		
					Indirect Cost (20%)		
					VAT: 5% x (DC + IC)		
					Total Item Cost		
2.6	Manual Cleaning and Removal of wastes and sludge	1	septic tank				
A	Labor		No. of septic tank	Unit	Unit Cost	Amount	
	Labor		1	septic tank			
					Sub-Total of A		
B	Equipment		Quantity	No. of days	Daily Rental	Amount	
	Minor Tools (10% of Labor Cost)		1	lot			
					Sub-Total of B		
					Direct Cost (A+B+C)		
					Indirect Cost (20%)		

				VAT: 5% x (DC + IC)			
				Total Item Cost			
III	Repair of leaks (Phase 2)						
3.1	Chipping Works	3.42	sq.m.				
A	Labor Unskilled	No. of Worker 1	No. of days 4	Daily Rate	Amount		
						Sub-Total of A	
B	Equipment Minor Tools (10% of Labor Cost)	Quantity 1	Unit lot	Unit Cost	Amount		
						Sub-Total of B	
						Direct Cost (A+B)	
						Indirect Cost (20%)	
						VAT: 5% x (DC + IC)	
						Total Item Cost	
3.2	Plumbing Works	1	lot				
Address leaks at female CR at Budget Section and male common CR, replace damaged parts and fixtures							
A	Material	Quantity	Unit	Unit Cost	Amount		
1" Ø Gate Valve for PPR		1	pc				
PPR Pipe 1" Ø		1	pc				
P-trap for urinal with complete fittings		1	set				
Waterproofing Sealant (85g)		1	tube				
Consumables (5% of materials cost)		1	lot				
						Sub-Total of A	
B	Labor Skilled Unskilled	No. of Worker 1 1	No. of days 3 3	Daily Rate	Amount		
						Sub-Total of B	
C	Equipment Minor Tools (10% of Labor Cost)	Quantity	Unit	Unit Cost	Amount		
						Sub-Total of C	
						Direct Cost (A+B+C)	
						Indirect Cost (20%)	
						VAT: 5% x (DC + IC)	
						Total Item Cost	
3.3	Tile Works	3.42	sq.m.				
A	Material	Quantity	Unit	Unit Cost	Amount		
30 X 60 cm Wall Tile		20	pc				
Tile Adhesive (25kg) - Heavy Duty		2	bag				
Consumables (5% of materials cost)		1	lot				
						Sub-Total of A	
B	Labor Skilled Unskilled	No. of Worker 1 1	No. of days 1 1	Daily Rate	Amount		
						Sub-Total of B	
C	Equipment Grinder	Quantity 1	No. of days 1	Daily Rental	Amount		
Minor Tools (10% of Labor Cost)		Quantity 1	Unit lot	Unit Cost	Amount		
						Sub-Total of C	
						Direct Cost (A+B+C)	
						Indirect Cost (20%)	
						VAT: 5% x (DC + IC)	
						Total Item Cost	
						Total Project Cost	

Submitted by:

Contractor's Authorized Representative